



- 1 **Headwork Building** - this building houses three internally fed drum screens with dewatering press augers. This system is used for the removal and dewatering of grit and screenings. Each screen has a capacity to process twelve million gallons per day. The dewatered material from the screen is emptied into dumpsters and taken to the landfill for disposal.